
TOWN OF LITTLETON, NH RIVERSIDE CULVERT REPLACEMENT

LITTLETON, NEW HAMPSHIRE
JUNE, 2024



OWNER:

TOWN OF LITTLETON
125 MAIN STREET, SUITE 200
LITTLETON NEW HAMPSHIRE, 03561
(603) 444-3996

ENGINEER:




34 SCHOOL STREET LITTLETON, NH 03561 (603) 444-4111




SURVEYOR:


HEADWATERS CONSULTING, LLC.
461 MAIN STREET
FRANCONIA, NEW HAMPSHIRE 03580

DATE OF PRINT
JUNE 25 2024




Z:\proj_2023\230740 Town of Littleton Riverside Drive Culvert\Internal\Civil\Final\230740_Final_2.dwg, EX-CON, 6/25/2024 1







Curtis Brook SEC 1-1 STA: 0+00 to STA: 0+21




Curtis Brook SEC 1-2 STA: 0+00 to STA: 0+28




STA: 0+00 to STA: 0+21



Curtis Brook SEC 1-2 (PROPOSED) STA: 0+00 to STA: 0+28



Curtis Brook SEC 1-3 (PROPOSED) STA: 0+00 to STA: 0+39



— EDGE OF WETLANDS

PHASING NOTES

- THE BELOW SUGGESTED PHASING PLAN SHALL BE USED UNLESS THE CONTRACTOR HAS DISCUSSED APPROVED ALTERNATIVE PHASING WITH THE ENGINEER.
- ESTABLISH TRAFFIC CONTROL AT DESIGNATED AREAS SHOWN ON THE PLAN AS WELL
- AS DETOUR SIGNAGE AT THE INTERSECTION OF RIVERSIDE DRIVE AND DEER COURT. DELINEATE THE LIMIT OF DISTURBANCE IN THE FIELD AS SHOWN ON THE PLANS.
- REMOVE GUARDRAIL SECTIONS AS NEEDED. SAW CUT AND REMOVE PAVEMENT AS SHOWN.
- CONSTRUCT LEVEL SPREADER AS SHOWN AND INSTALL WATER BYPASS PUMP AND
- 5.1. CONTRACTOR IS RESPONSIBLE FOR SIZING PUMP AND DISCHARGE LINE AS
- NECESSARY FOR THE FOLLOWING PARAMETERS. 5.1.1. CFS 0.51 (STREAM STATS 60% DURATION), BASE FLOW

Curtis Brook SEC 1-3

STA: 0+00 to STA: 0+39

- 5.1.2. CFS 2.00 (STORM EVENT SAFETY FACTOR, ENGINEER DETERMINED), DESIGN FLOW
- 6. CONSTRUCT COFFER DAM AS SHOWN. BEGIN CULVERT REMOVAL AND REPLACEMENT, TREE CLEARING, STONE ARMOUR BANK STABILIZATION, AND HEADWALL INSTALLATION.
- REMOVE COFFER DAM ONCE THE REPLACEMENT CULVERT HAS BEEN INSTALLED.
- RESTORE SURFACES AND REINSTALL GUARDRAIL SECTIONS.

FOR CONSTRUCTION



Civil and Structural Engineering Land Surveying and Environmental Consulting MAINE • NEW HAMPSHIRE • VERMONT www.horizonsengineering.com

TOWN OF LITTLETON, NH

RIVERSIDE CULVERT REPLACEMENT

LITTLETON, NEW HAMPSHIRE


CURTIS BROOK SECTIONS AND DEMO/PHASING PLAN

NO.	DATE	REVISION DESCRIPTION	ENG	DWG
1	06/2024	RFMI 1 RESPONSE - REMOVED WETLANDS IMPACTS, RECALCULATED DISTURBANCES	CLB	CLB

PROJECT #


230740





DATE OF PRINT JUNE 25 2024 HORIZONS ENGINEERING

© 2024 **horizons** Engineering All rights reserved




TERMINAL UNIT TYPE G-2 PER NHDOT SPECIFICATIONS

ITEM NO. 606.147


LEVEL LIP SPREADER INSTALLATION

- 1. CONSTRUCT THE LEVEL SPREADER LIP ON A ZERO PERCENT GRADE TO INSURE UNIFORM SPREADING OF RUNOFF.
- 2. LEVEL SPREADER SHALL BE CONSTRUCTED ON UNDISTURBED SOIL AND NOT ON FILL.
- 3. AN EROSION STOP SHALL BE PLACED VERTICALLY A MINIMUM OF SIX INCHES DEEP IN A SLIT TRENCH ONE FOOT BACK OF THE LEVEL LIP AND PARALLEL TO THE LIP. THE EROSION STOP SHALL EXTEND THE ENTIRE LENGTH OF THE LEVEL LIP.
- 4. THE ENTIRE LEVEL LIP AREA SHALL BE PROTECTED BY PLACING TWO STRIPS OF JUTE OR EXCELSIOR MATTING ALONG THE LIP. EACH STRIP SHALL OVERLAP THE EROSION STOP BY AT LEAST SIX INCHES.
- 5. THE ENTRANCE CHANNEL TO THE LEVEL SPREADER SHALL NOT EXCEED A 1 PERCENT GRADE FOR AT LEAST 50 FEET BEFORE ENTERING INTO THE SPREADER.
- 6. THE FLOW FROM THE LEVEL SPREADER SHALL OUTLET ONTO STABILIZED AREAS. WATER SHOULD NOT RE-CONCENTRATE IMMEDIATELY BELOW THE SPREADER.
- 7. PERIODIC INSPECTION AND REQUIRED MAINTENANCE SHALL BE PERFORMED.
- 8. PROTECTIVE MATERIAL AND EROSION STOP SHALL BE NORTH AMERICAN GREEN C125 EROSION CONTROL BLANKET OR APPROVED EQUAL.




LEVEL SPREADER DETAIL

NO SCALE
SOURCE: ROCKINGHAM COUNTY CONSERVATION SERVICE




SLOPED STONE ARMOR DETAIL

NOT TO SCALE



TYPICAL PAVEMENT SECTION

NOT TO SCALE




MATCH TOP OF BANK upstream and downstream — - PROVIDE 4" OF LOAM WITH MULCH OF WETLAND IMPACT AREA AND SEED TO DISTURBED AREAS -PROVIDE MINIMUM 18 INCHES OF CLASS B STONE FILL ON GEOTEXTILE FABRIC. KEY BASE OF STONE 2 FEET INTO UNDISTURBED GROUND. FILL VOIDS AND COVER STONE WITH FOUR INCHES OF LOAM, MATCH EXISTING MATCH EXISTING GRADE SEED AND MULCH AND PROTECT WITH NORTH UNLESS OTHERWISE AMERICAN DS 150 OR APPROVED EQUAL SPECIFIED - MIRAFI FILTERWEAVE FW 700 GEOTEXTILE FABRIC, OR EQUAL EXTEND TO GROUND SURFACE - EXISTING CHANNEL BOTTOM TO REMAIN UNDISTURBED WITH NATURAL SUBSTRATE

RESTORATION AT PERENNIAL STREAM SECTION

NOT TO SCALE

TYPICAL CUT PAVEMENT SECTION

NOT TO SCALE



COFFER DAM

NOT TO SCALE

COFFER DAM NOTES

- 1. CONSTRUCTION IS TO OCCUR DURING PERIOD OF LOW FLOWS IN BROOK CHANNEL. INSTALL LEVEL SPREADER AS SHOWN FOR DISCHARGE LOCATION.
- 2. PUMP SHALL BE SIZED BY THE CONTRACTOR.

LOCATION

- 4. CONSTRUCTION WITHIN THE CHANNEL SHALL NOT EXCEED THE ALLOWABLE DISTURBANCE AREA AS DESCRIBED IN THE STREAM ALTERATION PERMIT.
- 5. THE CONTRACTOR IS SOLELY
 RESPONSIBLE FOR CONTROLLING
 EROSION IN ALL AREAS DISTURBED BY
 HIS ACTIONS. COSTS FOR REQUIRED
 EROSION CONTROL, REGARDLESS OF
 WHETHER OR NOT SUCH MEASURES ARE
 SHOWN ON THE ENGINEERING
 DRAWINGS, SHALL BE BORNE BY HIM.

FOR CONSTRUCTION

horizons Engineering

Civil and Structural Engineering
Land Surveying and Environmental Consulting
MAINE • NEW HAMPSHIRE • VERMONT
www.horizonsengineering.com

TOWN OF LITTLETON, NH

RIVERSIDE CULVERT REPLACEMENT

LITTLETON, NEW HAMPSHIRE

DETAILS

NO.	DATE	REVISION DESCRIPTION	ENG	DW
1	06/2024	RFMI 1 RESPONSE - REMOVED WETLANDS IMPACTS, RECALCULATED DISTURBANCES	CLB	CLE

PROJECT #

230740

CLB

CHECK'D BY: ARCHIVE #

SHEET 5 OF 6

JUNE 2024

NGIN'D BY

CLB

MLB

OF PRINT
25 2024
ENGINEERING



DATE OF PRINT
JUNE 25 2024
HORIZONS ENGINEERING



0740 TOWILDI ENNEROIT KIVEISIDE DITVE CUIVEININE

© 2024 **horizens**Engineering
All rights reserved

1. GRADING AND SHAPING

A. SLOPES SHALL NOT BE STEEPER THAN 2:1; 3:1 SLOPES OR FLATTER ARE PREFERRED. WHERE MOWING WILL BE DONE, 3:1 SLOPES OR FLATTER ARE RECOMMENDED.

2. SEEDBED PREPARATION

A. SURFACE AND SEEPAGE WATER SHOULD BE DRAINED OR DIVERTED FROM THE SITE TO PREVENT DROWNING OR WINTER KILLING OF THE PLANTS.

B. STONES LARGER THAN 4 INCHES AND TRASH SHOULD BE REMOVED BECAUSE THEY INTERFERE WITH SEEDING AND FUTURE MAINTENANCE OF THE AREA. WHERE FEASIBLE, THE SOIL SHOULD BE AMENDED WITH ORGANIC MATTER AND TILLED TO A DEPTH OF ABOUT 4 INCHES TO PREPARE A SEEDBED AND MIX FERTILIZER AND LIME THOROUGHLY INTO THE SOIL. THE SEEDBED SHOULD BE LEFT IN A REASONABLY FIRM AND SMOOTH CONDITION. THE LAST TILLAGE OPERATION SHOULD BE PERFORMED ACROSS THE SLOPE WHEREVER

3. ESTABLISHING VEGETATION

A. LIME AND FERTILIZER SHOULD BE APPLIED PRIOR TO OR AT THE TIME OF SEEDING AND INCORPORATED INTO THE SOIL. KINDS AND AMOUNTS OF LIME AND FERTILIZER SHOULD BE BASED ON AN EVALUATION OF SOIL TESTS. WHEN A SOIL TEST IS NOT AVAILABLE, THE FOLLOWING MINIMUM AMOUNTS SHOULD BE APPLIED:

-AGRICULTURAL LIMESTONE, 2 TONS PER ACRE OR 100 LBS. PER 1,000 SQ. FT. -NITROGEN (N), 50 LBS., PER ACRE OR 1.1 LBS. PER 1,000 SQ. FT. -PHOSPHATE (P₂O₅), 100 LBS. PER ACRE OR 2.2 LBS. PER 1,000 SQ. FT.

-POTASH (K_20) , 100 LBS. PER ACRE OR 2.2 LBS. PER 1,000 SQ. FT.

(NOTE: THIS IS THE EQUIVALENT OF 500 LBS. PER ACRE OF 10-20-20 FERTILIZER OR 1,000 LBS. PER ACRE OF

B. SEED SHOULD BE SPREAD UNIFORMLY BY THE METHOD MOST APPROPRIATE FOR THE SITE. METHODS INCLUDE BROADCASTING, DRILLING, AND HYDROSEEDING. WHERE BROADCASTING IS USED, COVER SEED WITH .25 INCH OF SOIL OR LESS, BY CULTIPACKING OR RAKING.

C. SEEDING GUIDE:

	SEEDING		SOIL TYPE		
USE	MIXTURE (SEE 3D)	DROUGHTY	WELL DRAINED	MOD. WELL DRAINED	POORLY DRAINED
STEEP CUTS AND FILLS, BORROW AND DISPOSAL AREAS	A B C	FAIR POOR FAIR	GOOD GOOD EXCELLENT	GOOD FAIR EXCELLENT	FAIR FAIR POOR
WATERWAYS, EMERGENCY SPILL- WAYS, AND OTHER CHANNELS WITH FLOWING WATER	А	GOOD	GOOD	GOOD	FAIR
LIGHTLY USED PARKING LOTS, ODD AREAS, UNUSED LANDS, AND LOW INTENSITY USE RECREATION SITES	A B	GOOD GOOD	GOOD GOOD	GOOD FAIR	FAIR POOR

D. SEEDING RATES:

	MIXTURE	POUNDS PER ACRE	POUNDS PER 1,000 SQ. FT
Α	TALL FESCUE	20	0.45
	CREEPING RED FESCUE	20	0.45
	REDTOP	2	0.05
	TOTAL:	42	0.95
В	TALL FESCUE	15	0.35
	CREEPING RED FESCUE	10	0.25
	CROWN VETCH OR	15 OR	0.35 OR
	FLATPEA	30	0.75
	TOTAL:	40 OR 55	0.95 OR 1.35
С	TALL FESCUE	20	0.45
	FLATPEA	30	0.75
	TOTAL:	50	1.20

E. WHEN SEEDED AREAS ARE MULCHED, PLANTINGS MAY BE MADE FROM EARLY SPRING TO SEPTEMBER 15. WHEN SEEDED AREAS ARE NOT MULCHED, PLANTINGS SHOULD BE MADE FROM EARLY SPRING TO MAY 20 OR FROM AUGUST 10 TO SEPTEMBER 1.

F	F. TEMPORARY SEEDING RATES:							
	SPECIES	POUNDS PER ACRE	POUNDS PER 1,000 SQ. FT.	REMARKS				
	WINTER RYE	112	2.5	BEST FOR FALL SEEDING. SEED FROM AUGUST TO SEPTEMBER 5TH FOR BEST COVER. SEED TO A DEPTH OF 1 INCH.				
	OATS	80	2.0	BEST FOR SPRING SEEDING. SEED NO LATER THAN MAY 15TH FOR SUMMER PROTECTION. SEED TO A DEPTH OF 1 INCH.				
	ANNUAL RYEGRASS	40	1.0	GROWS QUICKLY, BUT IS OF SHORT DURATION. USE WHERE APPEARANCES ARE NOT IMPORTANT. SEED EARLY SPRING AND/OR BETWEEN AUGUST 15TH AND SEPTEMBER 15TH. COVER SEED WITH NO MORE THAN 0.25 INCH OF SOIL.				
-	PERENNIAL RYEGRASS	30	0.7	GOOD COVER WHICH IS LONGER LASTING THAN ANNUAL RYEGRASS. SEED BETWEEN APRIL 1ST AND JUNE 1ST AND/OR BETWEEN AUGUST 15TH AND SEPTEMBER 15TH. MULCHING WILL ALLOW SEEDING THROUGHOUT THE GROWING SEASON. SEED TO A DEPTH OF APPROXIMATELY 0.5 INCH.				

4. MULCH

A. HAY, STRAW, OR OTHER MULCH, WHEN NEEDED, SHOULD BE APPLIED IMMEDIATELY AFTER SEEDING.

B. MULCH WILL BE HELD IN PLACE USING APPROPRIATE TECHNIQUES FROM THE BEST MANAGEMENT PRACTICE FOR MULCHING.

5. MAINTENANCE TO ESTABLISH A STAND

- A. PLANTED AREAS SHOULD BE PROTECTED FROM DAMAGE BY FIRE, GRAZING, TRAFFIC, AND DENSE WEED
- B. FERTILIZATION NEEDS SHOULD BE DETERMINED BY ON SITE INSPECTIONS. SUPPLEMENTAL FERTILIZER IS USUALLY THE KEY TO FULLY COMPLETE THE ESTABLISHMENT OF THE STAND BECAUSE MOST PERENNIALS TAKE 2 TO 3 YEARS TO BECOME ESTABLISHED.
- C. IN WATERWAYS, CHANNELS, OR SWALES WHERE UNIFORM FLOW CONDITIONS ARE ANTICIPATED, OCCASIONAL MOWING MAY BE NECESSARY TO CONTROL GROWTH OF WOODY VEGETATION.

ļ	3" OVERLAP WHEN ————————————————————————————————————	— STAPLE ALL EDGES ON 12" CENTERS					
6" FOLDED UNDER TOP (& BOTTOM) OF SLOPE							
STAPLES ARE 12" APART ON INSIDE EDGES		STAPLE ALL EDGES ON 12" CENTERS					
ROLLMAX BIONET SC150BN OR - APPROVED EQUAL UNLESS OTHERWISE SPECIFIED ON THE PLANS. MATERIALS CONSISTING OF WELDED PLASTIC, PLASTIC, OR MULTI-FILAMENT OR MONOFILAMENT POLYPROPYLENE NETTING OR MESH SHALL BE PROHIBITED.	24" MAX.	6" OVERLAP WHEN JOINING ROLLS					
6" FOLDED UNDER BOTTOM (& TOP) OF SLOPE		NO STAPLES ARE TO BE OVER 24" APART (CENTER TO CENTER)					
<u></u>	1ULCH NETTING DETAIL SOURCE: USDA SOIL CONSERVATION SERVICE	ALL STAPLES TO BE 6 INCH STAPLES					
SOURCE: USDA SOIL CONSERVATION SERVICE							

NO SCALE

EROSION CONTROL GENERAL NOTES

A. KEEP SITE MODIFICATION TO A MINIMUM

- 1. CONSIDER FITTING THE BUILDINGS AND STREETS TO THE NATURAL TOPOGRAPHY. THIS REDUCES THE NEED FOR CUTS AND FILLS. AVOID EXTENSIVE GRADING THAT WOULD ALTER DRAINAGE PATTERNS OR CREATE VERY STEEP SLOPES.
- 2. EXPOSE AREAS OF BARE SOIL TO EROSIVE ELEMENTS FOR THE SHORTEST TIME POSSIBLE.
- 3. SAVE AND PROTECT DESIRABLE EXISTING VEGETATION WHERE POSSIBLE. ERECT BARRIERS 1. THE AREA OF EXPOSED, UNSTABILIZED SOIL SHALL BE LIMITED TO 1 ACRE AND SHALL BE TO PREVENT DAMAGE FROM CONSTRUCTION EQUIPMENT.
- 4. LIMIT THE GRADES OF SLOPES SO VEGETATION CAN BE EASILY ESTABLISHED AND
- 5. AVOID SUBSTANTIAL INCREASE IN RUNOFF LEAVING THE SITE.

B. MINIMIZE POLLUTION OF WATER DURING CONSTRUCTION ACTIVITIES

1. STOCKPILE TOPSOIL REMOVED FROM CONSTRUCTION AREA AND SPREAD OVER ANY DISTURBED AREAS PRIOR TO REVEGETATION. TOPSOIL STOCKPILES MUST BE PROTECTED FROM EROSION.

- 2. PROTECT BARE SOIL AREAS EXPOSED BY GRADING ACTIVITIES WITH TEMPORARY VEGETATION OR MULCHES.
- 3. USE SEDIMENT BASINS TO TRAP DEBRIS AND SEDIMENT WHICH WILL PREVENT THESE MATERIALS FROM MOVING OFF SITE.
- 4. USE DIVERSIONS TO DIRECT WATER AROUND THE CONSTRUCTION AREA AND AWAY FROM EROSION PRONE AREAS TO POINTS OF SAFE DISPOSAL.
- 5. USE TEMPORARY CULVERTS OR BRIDGES WHEN CROSSING STREAMS WITH EQUIPMENT.
- 6. PLACE CONSTRUCTION FACILITIES, MATERIALS, AND EQUIPMENT STORAGE AND MAINTENANCE AREAS AWAY FROM DRAINAGE WAYS.

C. PROTECT AREA AFTER CONSTRUCTION.

- 1. ESTABLISH GRASS OR OTHER SUITABLE VEGETATION ON ALL DISTURBED AREAS. SELECT SPECIES ADAPTED TO THE SITE CONDITIONS AND THE FUTURE USE OF THE AREA. FINAL GRADES SHALL BE SEEDED WITHIN 72 HOURS. STABILIZATION SHALL BE DEFINED AS 85% VEGETATIVE COVER.
- 2. MAINTAIN VEGETATED AREAS USING PROPER VEGETATIVE 'BEST MANAGEMENT PRACTICES' DURING THE CONSTRUCTION PERIOD.
- 3. MAINTAIN NEEDED STRUCTURAL 'BEST MANAGEMENT PRACTICES' AND REMOVE SEDIMENT FROM DETENTION PONDS AND SEDIMENT BASINS AS NEEDED.
- 4. DETERMINE RESPONSIBILITY FOR LONG TERM MAINTENANCE OF PERMANENT 'BEST MANAGEMENT PRACTICES'.
- 5. IF CONSTRUCTION IS ANTICIPATED DURING WINTER MONTHS, REFER TO 'COLD WEATHER SITE STABILIZATION REQUIREMENTS'.

D. INVASIVE SPECIES AND FUGITIVE DUST

1. THE PROJECT SHALL NOT CONTRIBUTE TO THE SPREAD OF INVASIVE SPECIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL EVALUATE WORK AREAS FOR THE PRESENCE OF INVASIVE SPECIES, AND IF FOUND SHALL TAKE NECESSARY MEASURES TO PREVENT THEIR SPREAD IN ACCORDANCE WITH RSA 430:51-57 AND AGR 3800. THE CONTRACTOR SHALL TAKE ALL NECESSARY MEASURES TO PREVENT THE INTRODUCTION OF INVASIVE SPECIES BY INSPECTING AND CLEANING ALL EQUIPMENT ARRIVING ON SITE.


2. FUGITIVE DUST SHALL BE CONTROLLED IN ACCORDANCE WITH ENV-A 1000

COLD WEATHER SITE STABILIZATION **REQUIREMENTS**

- TO ADEQUATELY PROTECT WATER QUALITY DURING COLD WEATHER AND
- PROTECTED AGAINST EROSION BY THE METHODS DESCRIBED IN THIS SECTION PRIOR TO ANY THAW OR SPRING MELT EVENT. THE ALLOWABLE AREA OF EXPOSED SOIL MAY BE CPESC SPECIALIST, IS REVIEWED AND APPROVED BY NHDES.
- 2. ALL PROPOSED VEGETATED AREAS HAVING A SLOPE OF LESS THAN 15% WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE GROWTH BY OCTOBER 15, OR WHICH ARE INCHES OF EROSION CONTROL MIX MEETING THE CRITERIA OF ENV-WQ 1506.05(D)
- 3. ALL PROPOSED VEGETATED AREAS HAVING A SLOPE OF GREATER THAN 15% WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE GROWTH BY OCTOBER 15, OR WHICH ARE DISTURBED AFTER OCTOBER 15, SHALL BE SEEDED AND COVERED WITH PROPERLY INSTALLED AND ANCHORED EROSION CONTROL MATTING OR WITH A MINIMUM 4 INCH THICKNESS OF EROSION CONTROL MIX MEETING THE CRITERIA OF ENV-WQ 1506.05(D)
- 4. INSTALLATION OF ANCHORED HAY MULCH OR EROSION CONTROL MIX, MEETING THE CRITERIA OF ENV-WQ 1506.05(D) THROUGH (H), SHALL NOT OCCUR OVER SNOW OF GREATER THAN 1 INCH IN DEPTH.
- 5. INSTALLATION OF EROSION CONTROL MATTING SHALL NOT OCCUR OVER SNOW OF GREATER THAN ONE INCH IN DEPTH OR ON FROZEN GROUND.
- COMPLETED WITHIN 1 DAY OF ESTABLISHING THE GRADE THAT IS FINAL OR THAT OTHERWISE WILL EXIST FOR MORE THAN 5 DAYS.
- 7. ALL DITCHES OR SWALES WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE GROWTH BY OCTOBER 15, OR WHICH ARE DISTURBED AFTER OCTOBER 15, SHALL BE FOR THE DESIGN FLOW CONDITIONS, AS DETERMINED BY THE OWNER'S ENGINEERING CONSULTANT.
- 8. AFTER OCTOBER 15, INCOMPLETE ROAD OR PARKING AREAS WHERE ACTIVE CONSTRUCTION OF THE ROAD OR PARKING AREA HAS STOPPED FOR THE WINTER SEASON SHALL BE PROTECTED WITH A MINIMUM 3 INCH LAYER OF BASE COURSE GRAVELS MEETING THE GRADATION REQUIREMENTS OF NHDOT STANDARD SPECIFICATION FOR ROAD AND BRIDGE CONSTRUCTION, 2016, ITEM NO. 304.1 OR 304.2.

LEVEL LIP SPREADER INSTALLATION

- 1. CONSTRUCT THE LEVEL SPREADER LIP ON A ZERO PERCENT GRADE TO INSURE UNIFORM SPREADING OF RUNOFF.
- 2. LEVEL SPREADER SHALL BE CONSTRUCTED ON UNDISTURBED SOIL AND NOT ON
- 3. AN EROSION STOP SHALL BE PLACED VERTICALLY A MINIMUM OF SIX INCHES DEEP IN A SLIT TRENCH ONE FOOT BACK OF THE LEVEL LIP AND PARALLEL TO THE LIP. THE EROSION STOP SHALL EXTEND THE ENTIRE LENGTH OF THE LEVEL LIP.
- 4. THE ENTIRE LEVEL LIP AREA SHALL BE PROTECTED BY PLACING TWO STRIPS OF JUTE OR EXCELSIOR MATTING ALONG THE LIP. EACH STRIP SHALL OVERLAP THE EROSION STOP BY AT LEAST SIX INCHES.
- 5. THE ENTRANCE CHANNEL TO THE LEVEL SPREADER SHALL NOT EXCEED A 1 PERCENT GRADE FOR AT LEAST 50 FEET BEFORE ENTERING INTO THE SPREADER.
- 6. THE FLOW FROM THE LEVEL SPREADER SHALL OUTLET ONTO STABILIZED AREAS. WATER SHOULD NOT RE-CONCENTRATE IMMEDIATELY BELOW THE SPREADER.
- 7. PERIODIC INSPECTION AND REQUIRED MAINTENANCE SHALL BE PERFORMED.
- 8. PROTECTIVE MATERIAL AND EROSION STOP SHALL BE NORTH AMERICAN GREEN C125 EROSION CONTROL BLANKET OR APPROVED EQUAL



2. SLOPE SURFACE SHALL BE FREE OF ROCKS, CLODS, STICKS AND GRASS. MATS/BLANKETS SHALL HAVE GOOD SOIL CONTACT.

3. APPLY PERMANENT SEEDING BEFORE PLACING BLANKETS.

-EXISTING GROUND

— EXISTING GROUND

FILTER CLOTH -

4. LAY BLANKETS LOOSELY AND STAKE OR STAPLE TO MAINTAIN DIRECT CONTACT WITH THE SOIL. DO NOT STRETCH.

75' MIN. WITHOUT MOUNTABLE BERM

50' MIN. WITH MOUNTABLE BERM

PROFILE

PLAN

DETAIL DIGITIZED FROM NEW HAMPSHIRE STORMWATER MANUAL, VOLUME 3, NHDES 2008

MANDATORY

MOUNTABLE BERM FOR ENTRANCES

50' TO 74' LONG

EROSION CONTROL BLANKET INSTALLATION DETAIL

EXISTING PAVEMENT

10'

FOR CONSTRUCTION

CONSTRUCTION SEQUENCE

1. PREPARE AN EROSION CONTROL PLAN OR A STORMWATER POLLUTION PREVENTION

2. INSTALL CONSTRUCTION ENTRANCE, SEE DETAIL.

5. GRUB SITE WITHIN GRADING LIMITS.

ACHIEVING FINISHED GRADE.

BALES, ETC., AS NECESSARY.

13. PLACE TOPSOIL, SEED AND MULCH.

IS ESTABLISHED.

12. PAVE ROADWAYS AND/OR PARKING AREAS.

RIPRAP HAS BEEN INSTALLED: OR

3. CUT AND CLEAR TREES WITHIN THE CLEARING LIMITS.

LEVEL SPREADERS UNTIL THEY HAVE BEEN STABILIZED.

PLAN (SWPPP) IN ACCORDANCE WITH LOCAL, STATE, AND FEDERAL REQUIREMENTS.

4. INSTALL SEDIMENT FENCES, ROCK CHECK DAMS, AND OTHER APPROPRIATE EROSION

CONTROL MEASURES AT LOCATIONS SHOWN ON THE PLANS AND AS NEEDED.

6. STRIP AND STOCKPILE TOPSOIL AND INSTALL EROSION CONTROL MEASURES.

7. INSTALL/ADJUST SEDIMENT FENCE, CHECK DAMS, AND HAYBALES, AS REQUIRED.

8. CONSTRUCT PERMANENT STORMWATER CONTROLS AS SOON AS PRACTICAL. DO NOT

DIRECT STORMWATER TOWARD TREATMENT BASINS, PONDS, SWALES, DITCHES AND

9. PROCEED WITH WORK, LIMITING THE DURATION OF DISTURBANCE. THE MAXIMUM OF

UNCOVERED DISTURBED EARTH AT ANY ONE TIME IS FIVE ACRES. THE MAXIMUM

10. BEGIN SEEDING AND MULCHING IMMEDIATELY AFTER GRADING. ALL DISTURBED

AREAS SHALL BE STABILIZED WITH APPROVED METHODS WITHIN 72 HOURS OF

A) BASE COURSE GRAVELS HAVE BEEN INSTALLED IN AREAS TO BE PAVED;

11. INSPECT ALL EROSION CONTROL MEASURES ON A DAILY BASIS AND AFTER EVERY 0.5

INCHES OF PRECIPITATION. MAINTAIN SEDIMENT FENCE, SEDIMENT TRAPS, HAY

15. MONITOR THE SITE AND MAINTAIN STRUCTURES AS NEEDED UNTIL FULL VEGETATION

17. NO STORAGE OF FUEL SHALL OCCUR WITHIN 25 FEET OF JURISDICTIONAL WETLANDS.

16. NO REFUELING OF EQUIPMENT SHALL OCCUR WITHIN JURISDICTIONAL WETLANDS.

B) A MINIMUM OF 85% VEGETATED GROWTH HAS BEEN ESTABLISHED;

C) A MINIMUM OF 3" OF NON-EROSIVE MATERIAL SUCH AS STONE OR

D) EROSION CONTROL BLANKETS HAVE BEEN PROPERLY INSTALLED.

14. COMPLETE ALL REMAINING PERMANENT EROSION CONTROL STRUCTURES.

AN AREA SHALL BE CONSIDERED STABLE IF ONE OF THE FOLLOWING HAS OCCURRED:

LENGTH OF TIME THAT DISTURBED EARTH MAY BE LEFT UNSTABILIZED IS 45 DAYS.

Engineering **Civil and Structural Engineering**

Land Surveying and Environmental Consulting MAINE • NEW HAMPSHIRE • VERMONT www.horizonsengineering.com

TOWN OF LITTLETON, NH

RIVERSIDE CULVERT REPLACEMENT

LITTLETON, NEW HAMPSHIRE

EROSION CONTROL NOTES AND DETAILS


NO.	DATE	REVISION DESCRIPTION				DWG
1	06/2024	RFMI 1 RESPONSE - REMOVED WETLANDS IMPACTS, RECALCULATED DISTURBANCES			CLB	CLB
:*********			DATE:	F	PROJE	CT #:



JUNE 2024 230740 CLB HECK'D B' MLB SHEET 6 OF 6

- DURING SPRING RUNOFF, THE FOLLOWING ADDITIONAL STABILIZATION TECHNIQUES SHALL BE EMPLOYED DURING THE PERIOD FROM OCTOBER 15 THROUGH MAY 1:
- INCREASED IF A WINTER CONSTRUCTION PLAN, DEVELOPED BY A QUALIFIED ENGINEER OR A
- DISTURBED AFTER OCTOBER 15, SHALL BE SEEDED AND COVERED WITH 3 TO 4 TONS OF HAY OR STRAW MULCH PER ACRE, SECURED WITH ANCHORED NETTING OR TACKIFIER, OR 2 THROUGH (H).
- THROUGH (H).
- 6. ALL PROPOSED STABILIZATION IN ACCORDANCE WITH NOTES 2 OR 3 ABOVE, SHALL BE
- STABILIZED TEMPORARILY WITH STONE OR EROSION CONTROL BLANKETS APPROPRIATE

- 36" MIN FENCE POSTS DRIVEN MIN. 16" INTO GROUND CONSTRUCTION NOTES FOR SEDIMENT FENCE WOVEN WIRE FENCE -. WOVEN WIRE FENCE, IF REQUIRED, (14-1/2 GA. MIN., TO BE FASTENED SECURELY TO FENCE MAX. 6" MESH SPACING) WITH FILTER CLOTH OVER POSTS WITH WIRE TIES OR STAPLES. 2. FILTER CLOTH TO BE FASTENED SECURELY TO WOVEN WIRE FENCE WITH TIES SPACED EVERY 24" AT TOP, MID SECTION, AND BOTTOM. 3. WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER, THEY SHALL BE OVERLAPPED BY 6 INCHES, FOLDED AND STAPLED. 4. MAINTENANCE SHALL BE PERFORMED AS NEEDED AND MATERIAL REMOVED WHEN "BULGES" DEVELOP IN THE SEDIMENT FENCE, OR 50% OF CAPACITY IS USED. 5. 12" DIAMETER FILTREXX SILTSOXX UNDISTURBED GROUND -SHALL BE CONSIDERED AN ACCEPTABLE EQUAL TO SEDIMENT FENCE IF INSTALLED PER MANUFACTURER'S EMBED FILTER CLOTH -MIN. 8" INTO GROUND RECOMMENDATIONS. SEDIMENT FENCE



STABILIZED CONSTRUCTION ENTRANCE NOT TO SCALE

8" MIN.—

50' MIN. (SEE NOTES ABOVE)

- CLASS C STONE FILL-ITEM 585.3, MINIMUM

STONE SIZÉ 3 INCHES

DATE OF PRINT JUNE 25 2024 HORIZONS ENGINEERING

hogizens All rights reserved